

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE	PAGE 1 OF 2 PAGES
2. AMENDMENT/MODIFICATION NO. AMENDMENT NO. 0003		3. EFFECTIVE DATE 08-26-10	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. (If applicable) 09-0151
6. ISSUED BY CODE ltc Officer in Charge of Construction MCI-East 1005 Michael Road Camp Lejeune, NC 28547-2521		7. ADMINISTERED BY (If other than Item 6) CODE See Item 6		
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)			(X)	9A. AMENDMENT OF SOLICITATION NO. N40085-09-R-0151
			X	9B. DATED (SEE ITEM 11) 08-16-10
				10A. MODIFICATION OF CONTRACT/ORDER NO.
				10B. DATED (SEE ITEM 11)
CODE	FACILITY CODE			

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers is extended, is not extended.
 Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:
 (a) By completing items 8 and 15, and returning 0 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted;
 or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment your desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

**13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.**

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor is not, is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

09-0151, Repair HVAC System, Bldg 84

SEE CONTINUATION SHEET

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR (Signature of person authorized to sign)		16B. UNITED STATES OF AMERICA (Signature of Contracting Officer)	
15C. DATE SIGNED		16C. DATE SIGNED	

CONTINUATION SHEET

Question 1: Drawing E5.02 Panel F shows a 250/3 circuit breaker to be installed in an existing NQOB panel. I am being told by my vendors that a 150 amp breaker would be the largest breaker they can provide for an NQOB panel and that it would take up six spaces as well. Could more information on the breaker requirements be provided for the 250/3 breaker for AHU-11 in panel F?

Answer 1: Field notes indicate that in the bottom section of Panelboard "F", below the branch circuit breakers, there are two (2) spaces available for two (2) sub-feed circuit breakers. There is one existing 3P. 225A circuit breaker and space for a second 3P. 225A. breaker. However, to avoid possibly loading Panel "F" to its maximum, it is recommended that the following be changed: In lieu of running the feeder to Panel "F", extend the feeder to Panel P4 located on drawing E2.01.

Question 2: Spec Sec 02 82 16, para 1.4.1 references removal of all domestic cold water piping insulation & pipe insulation in Bldg 825. However, there is nothing in the DWGS that refers to these items. Are these items supposed to be removed?

Answer 2: Removal of domestic water pipe insulation as noted in the specifications is not required.

Question 3: Spec 01 14 00, 1.2.5 note c tells us that Interruption to water, sanitary sewer, storm drain, telephone, electric, air conditioning, heating, fire alarm, and compressed air shall be considered utility cutovers pursuant to the paragraph "Work Outside Regular Hours." Is it the intent for this job to be done outside regular working hours since the entire job is interrupting the AC/heat?

Answer 3: This work will be performed during regular working hours. All outages will need to be programmed by the contractor in his construction schedule and coordinated with the contracting officer.